

OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
PONTOTOC COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Pontotoc County, Mississippi at the Pontotoc County Chancery Building, Pontotoc, Mississippi, until on the day of , and shortly thereafter publicly opened for the construction of 0.100 miles of BRIDGE & APPROACHES TO REPLACE BRIDGE NO. 93 on OLD HIGHWAY 6 being known as ERBR2.0 PROJECT **CRSA-0070-00(025) LPA 109112-701000** in Pontotoc County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

| ITEM   | QUANTITY | UNIT |
|--|----------|------|
| <u>ROADWAY ITEMS:</u>  |          |      |
| MOBILIZATION   | LUMP SUM | LS   |
| CLEARING AND GRUBBING  | LUMP SUM | LS   |
| REMOVAL OF BRIDGE AT STA 145+40                                    | 1.000    | EA   |
| UNCLASSIFIED EXCAVATION (FM)                                       | 26.000   | CY   |
| BORROW EXCAVATION (F.M.E.)<br>(CONTRACTOR FURNISHED) (CLASS 9)     | 158.000  | CY   |
| GRANULAR MATERIAL (FM),<br>(CLASS 9, GROUP B)                      | 53.000   | CY   |
| GRANULAR MATERIAL (FM),<br>(CLASS 5, GROUP C)                      | 7.000    | CY   |
| CRUSHED STONE (Size ¾" & Down)(FM)                                 | 70.01    | CY   |
| HOT MIX ASPHALT, ST, 9.5 MM  | 35.00    | TON  |
| HOT MIX ASPHALT, ST, 12 MM   | 52.00    | TON  |
| GUARD RAIL, "W" BEAM   | 275.00   | LF   |
| GUARD RAIL, BRIDGE END SECTION,<br>TYPE THRIE BEAM 1               | 4.00     | EA   |
| GUARD RAIL, TERMINAL END SECTION                                   | 4.00     | EA   |
| MAINTENANCE OF TRAFFIC   | LUMP SUM | LS   |
| ADDITIONAL CONSTRUCTION SIGNS                                      | 0.000    | SF   |
| REFLECTORIZED TRAFFIC OBJECT MARKER<br>(ENCAPSULATED LENS)(TYPE 3) | 4.000    | EA   |
| <u>EROSION CONTROL ITEMS:</u>                                      |          |      |
| AGRICULTURAL LIMESTONE   | 0.250    | TON  |
| COMMERCIAL FERTILIZER (13-13-13)                                   | 0.250    | TON  |
| AMMONIUM NITRATE   | 0.250    | TON  |
| SEEDING  | 0.110    | AC   |

|                                |         |     |
|--------------------------------|---------|-----|
| VEGETATIVE MATERIALS FOR MULCH | 0.250   | TON |
| SOLID SODDING                  | 100.000 | SY  |

|  |           |    |
|--|-----------|----|
| TEMPORARY SILT FENCE<br>(TYPE I OR II) (AOS 0.15-0.84) | 1,100.000 | LF |
| Wattles, 20"   | 50.000    | LF |

BRIDGE ITEMS:

|   |            |     |
|---|------------|-----|
| STA. 145=40, 1@40, 1@100, 2@31' PRESTRESSED CONCRETE SPAN |            |     |
| 28' CLEAR ROADWAY, 202.01' ALONG CENTERLINE               |            |     |
| TEST PILES  | 2.000      | EA  |
| CONVENTIONAL STATIC PILE LOAD TESTS                       | 2.000      | EA  |
| 14" STEEL PILING  | 2,275.000  | LF  |
| 16" PRE-FORMED PILE HOLES                                 | 2,031.000  | LF  |
| BRIDGE CONCRETE, CLASS "A"                                | 254.040    | CY  |
| REINFORCEMENT   | 40,337.000 | LB  |
| 31' PRESTRESSED CONCRETE BEAMS                            | 307.50     | LF  |
| 40' PRESTRESSED CONCRETE BEAMS                            | 198.75     | LF  |
| 100' PRESTRESSED CONCRETE BEAMS                           | 498.75     | LF  |
| CONCRETE BARRIER RAIL                                     | 404.000    | LF  |
| STRUCTURAL STEEL  | 6,113.750  | LB  |
| LOOSE RIPRAP, 300 LB.                                     | 730.000    | TON |
| GEOTEXTILE UNDER RIPRAP,<br>TYPE V, AOS 0.21-0.43         | 1,081.000  | SY  |

PROJECT NO. **CRSA-0070-00(025) LPA 109112-701000**  
PONTOTOC COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 210 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement; minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Pontotoc County, the County Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Michael J. Falkner at [www.esiplans.com](http://www.esiplans.com). PLANS AND PROPOSALS may also be downloaded electronically by Bidders for electronic bidding purposes ONLY. Questions regarding electronic bidding shall be directed to Plan House Printing at (662) 407-0193.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Pontotoc County and the State of Mississippi must accompany each proposal. For Bidders submitting bids electronically, the bond submitted must be either a bond issued by the Surety in electronic format or the original hard copy of the bid bond must be submitted to the Pontotoc County Board of Supervisors, Pontotoc, Mississippi prior to bid opening in order for the bid to be valid.

The entire PROPOSAL is required to be turned in for both paper and electronic bid submission.

Brad Ward, President  
Pontotoc County Board of Supervisors