Notice of Advertisement Project No. ERBR-31(02) Jasper County, MS

## JASPER COUNTY BOARD OF SUPERVISORS COUNTY PROJECT NO. ERBR-31(02)

# NOTICE OF ADVERTISEMENT

#### NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Jasper County, Mississippi at the Jasper County Courthouse, Bay Springs, Mississippi, until 10:00 AM on the 27<sup>th</sup> day of September 2024 and shortly thereafter publicly opened for the construction of 0.264 miles at Bridge "A" on CR 16, 0.013 miles of 1@19', 1@31', 1@19' PC concrete span bridge and approaches at Bridge "B" 3@40', 1@80', 3@40' prestressed concrete beam span bridge and approaches, being known as County Project No. ERBR-31(02) in Jasper County Mississippi.

## PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ROADWAY ITEMS	QUANTITY	UNIT
MOBILIZATION	LUMP SUM	LS
CLEARING & GRUBBING	LUMP SUM	LS
REMOVAL OF OBSTRUCTIONS	LUMP SUM	LS
REMOVAL OF BRIDGE @ STA. 43+98.50	1.0	EA
REMOVAL OF BRIDGE @ STA. 48+35.75	1.0	EA
BORROW EXCAVATION, (FME) (CONTRACTOR FURNISHED) (CLASS 9)	1,855.0	C.Y.
EXCESS EXCAVATION (FM)	464.0	C.Y.
GRANULAR MATERIAL (LVM) (CLASS 9, GROUP B)	909.0	C.Y.
HOT BITUMINOUS PAVEMENT BASE COURSE (BB-1)	232.0	Т
HOT BITUMINOUS PAVEMENT SURFACE COURSE, (SC-1) (TYPE B)	219.0	Т
GUARD RAIL, "W" BEAM COMPLETE IN PLACE	200.0	L.F.
GUARD RAIL, BRIDGE END SECTION, TYPE "I", THRIE BEAM	8.0	EA
GUARD RAIL, TERMINAL END SECTION	8.0	EA
ROADWAY CONSTRUCTION SURVEYING	LUMP SUM	LS
RIGHT-OF-WAY MARKERS (TYPE II)	4.0	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.0	S.F.
4" WIDE COLD PLASTIC TRAFFIC STRIPE (SKIP YELLOW)	0.069	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (120 MIL)	0.154	MI
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	45.0	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)	8.0	EA
	0.0	
EROSION CONTROL ITEMS		
AGRICULTURAL LIMESTONE	6.2	Т
COMMERCIAL FERTILIZER (13:13:13)	3.1	Т
AMMONIUM NITRATE	0.46	Т
SEEDING	3.1	AC
VEGETATIVE MATERIALS FOR MULCH	6.2	Т
SOLID SODDING	165.0	S.Y.
PORTLAND CEMENT CONCRETE PAVED DITCH	8.0	C.Y.
TEMPORARY SILT FENCE (TYPE II)(AOS 0.16-0.84)	2,500.0	L.F.
LOOSE RIPRAP, 200LB	130.0	Т
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	330.0	S.Y.
WATTLES, 20"	350.0	L.F.

BRIDGE "A" ITEMS	QUANTITY	UNIT
TEST PILE	2.0	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.0	EA
14" PRESTRESSED CONCRETE PILING	790.0	L.F.
18" PREFORMED PILE HOLES	454.0	L.F.
19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	12.0	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.0	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.0	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' UNIT EXTERIOR	2.0	EA
PRECAST CONCRETE BARRIER RAIL	138.0	L.F.
31.0' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.0	EA
31.0' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.0	EA
9.25' PRECAST CONCRETE WIND	4.0	EA
LOOSE RIPRAP, 300LB	197.0	Т
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	465.0	S.Y.
BRIDGE "B" ITEMS		
	2.0	

TEST PILE	3.0	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.0	EA
14" PRESTRESSED CONCRETE PILING	2,160.0	L.F.
16" PRESTRESSED CONCRETE PILING	1,300.0	L.F.
18" PREFORMED PILE HOLES	600.0	L.F.
20" PREFORMED PILE HOLES	504.0	L.F.
BRIDGE CONCRETE, CLASS "A"	339.63	C.Y.
40' PRESTRESSED CONCRETE BEAM, TYPE 1+2	1,192.5	L.F.
80' PRESTRESSED CONCRETE BEAM, TYPE III	398.75	L.F.
REINFORCEMENT	62,131.0	LB
CONCRETE RAILING	640.0	L.F.
LOOSE RIPRAP, 300LB	290.0	Т
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	656.0	S.Y.

## NOTICE TO CONTRACTORS:

CONTRACT TIME:

180 Working Days

#### BASIS OF AWARD:

The award, if made, will be made to the lowest qualified bidder on the basis of the published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that, in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for an award.

This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS, SPECIFICATIONS, AND PROPOSALS are on file and can be viewed and obtained online via the website of the County Engineer, Lawrence R. Clark, P.E. at www.clarkengineersprojects.com. By use of the website the plan holders shall have the option of obtaining hard copy of the Plans and Specifications and/or shall have the opportunity to submit an official bid online.

All hard copy proposals shall be directed to the attention of The Jasper County Board of Supervisors with the outside of the envelope marked "ERBR-31(02) BRIDGE PROJECT". Contractor shall indicate certificate of responsibility number on the outside of the envelope. Online bids shall be accepted and opened as instructed on the website.

Certified Check or Bid Bond for five percent (5%) of total bid payable to Jasper County must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letter qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid, and such proposals will not be considered in making the award.

State Aid is not a party to this contract or the project.

Doug Rogers, President Jasper County Board of Supervisors State of Mississippi

Publish Dates: Wednesday, August 21, 2024 Wednesday, August 28, 2024