

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Simpson County Mississippi at the Chancery Court Building, 111 West Pine Avenue, Mendenhall, Mississippi, until 9:30 AM on the 9th day of August, 2024 and shortly thereafter publicly opened for the construction of 0.075 miles of BRIDGE REPLACEMENT AND APPROACHES on the New Hope Road being known as Project No. ERBR-64(05) in Simpson County Mississippi.

CONTRACT TIME: 80 Working Days

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities. Simpson County reserves the right to waive any information or irregularities or to reject any or all bids.

The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement; minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Simpson County and the Office of Greg Bonds, the County Engineer, 660 Katherine Drive, Suite 302, Flowood, MS 39232. Plans and specifications can also be viewed on the Simpson County website (simpsoncountymiss.com) by clicking Online Bidding. Hard copies of the plans and contract documents may be obtained from the office of Benchmark Engineering & Surveying, LLC, at the address listed above upon payment of \$150 for each set, none of which is refundable.

Sealed bids shall be submitted in person as required or on-line at bids.simpsoncountymiss.com (Bidder responsible to any online bidding fees). This project shall be constructed in accordance with the latest edition of the MS Standard Specifications for State Aid Road and Bridge Construction.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Simpson County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Mitchell Chatman, President
Simpson County Board of Supervisors

Published: Magee Courier-Simpson County News
July 11th, 2024
July 18th, 2024

For the construction of: BRIDGE & APPROACHES on 0.075 mile(s) of county road(s) known as New Hope Road in Simpson County, Mississippi under ERBR-64(05)
I (We) agree to complete the entire project within 80 Working Days.

SPECIAL NOTICE TO BIDDERS

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price	Item Total
Roadway Items						
1	S-200-A	MOBILIZATION	1.000	LS		
2	S-201-A	CLEARING AND GRUBBING	1.000	LS		
3	S-202-B	REMOVAL OF BRIDGE @ STA. 225+02.46	1.000	UN		
4	S-202-D	REMOVAL OF EXIST PAVEMENT (ALL DEPTHS)	22.000	SY		
5	S-203-A	UNCLASSIFIED EXCAVATION (FM)	226.000	CY		
6	S-203-E1	BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	400.000	CY		
7	S-203-H	EXCESS EXCAVATION (LVM)	100.000	CY		
8	S-304-A	GRANULAR MATERIAL (LVM), (CLASS 5, GROUP C)	91.000	CY		
9	S-304-D	CRUSHED STONE	67.000	TON		
10	S-403-A	HOT MIX ASPHALT, (ST.) (12.5 mm)	87.000	TON		
11	S-403-A	HOT MIX ASPHALT, (ST.) (19 mm)	33.000	TON		
12	S-406-A	COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	200.000	SY		
13	S-607-A	CONSTRUCTION SURVEYING	1.000	LS		
14	S-618-A	MAINTENANCE OF TRAFFIC	1.000	LS		

15	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0.000	SF		
16	S-621-C	4 in WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (90 mils)	0.150	MI		
17	S-621-E-1	4 in WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (120 mils)	792.000	LF		
18	S-627-L	TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	6.000	EA		
19	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA		
Subtotal Participating Roadway Items						

Erosion Control Items

20	901-S-212-A	AGRICULTURAL LIMESTONE	0.500	TON		
21	S-212-B	COMMERCIAL FERTILIZER (13-13-13)	0.250	TON		
22	S-212-F	AMMONIUM NITRATE	0.250	TON		
23	S-214-A	SEEDING	0.250	AC		
24	S-215-A	VEGETATIVE MATERIALS FOR MULCH	0.750	TON		
25	S-233-A	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)	792.000	LF		
26	237-A	WATTLES, 20 in DIAMETER	160.000	LF		
27	S-815-A	LOOSE RIPRAP, 300 LB.	562.000	TON		
28	S-815-E	GEOTEXTILE FABRIC UNDER RIPRAP,TYPE V (AOS 0.31 -0.43)	494.000	SY		
Subtotal Participating Erosion Control Items						

Bridge Items

29	S-803-A	TEST PILE	2.000	EA		
30	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA		
31	S-803-C	14 in PRESTRESSED CONCRETE PILING	800.000	LF		

32	S-803-F	18 in PRE-FORMED PILE HOLES	200.000	LF		
33	S-806-A	19 ft PRECAST CONCRETE SLAB UNIT, 3.5 ft INTERIOR	24.000	EA		
34	S-806-C	31 ft PRECAST CONCRETE SLAB UNIT, 3.5 ft EXTERIOR	8.000	EA		
35	S-806-G	PRECAST CONCRETE BARRIER RAIL	248.000	LF		
36	S-806-I	31 ft PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	3.000	EA		
37	S-806-J	31 ft PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA		
38	S-806-M	PRECAST CONCRETE WING	4.000	EA		

Subtotal Participating Bridge Items

--

TOTAL BID AMOUNT

--