

**OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
YAZOO COUNTY BOARD OF SUPERVISORS**

SECTION 900

NOTICE TO CONTRACTORS :

Sealed bids will be received by the Board of Supervisors of Yazoo County, Mississippi at the Yazoo County Administrative Building, Yazoo City, Mississippi, until 10:00 AM on the 7th day of December, 2020 and shortly thereafter publicly opened for the construction of 0.434 miles of BRIDGE AND APPROACHES on Anding Oil City Road being known as Project No. ERBR-82(02) in Yazoo County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS :</u>		
Mobilization	Lump Sum	L.S.
Clearing and Grubbing	Lump Sum	L.S.
Removal of Buried Butane Tank @ Sta. 387+63.00	1	Unit
Removal of Timber Bridge at Sta. 384+40.00	1	Unit
Removal of Timber Box Culvert @ Sta. 384+27.00	162.0	L.F.
Removal of Asphalt (All Depths)	5,253.0	S.Y.
Removal of Pipe (All Sizes)	334.0	L.F.
Unclassified Excavation (F.M.)	13,003.0	C.Y.
Borrowed Excavation (F.M.E.) (Contractor Furnished) (Class 9)	4,546.0	C.Y.
Channel Excavation (F.M.)	1,473.0	C.Y.
Structure Excavation	948.0	C.Y.
Granular Material LVM (Cl. 4, Gp. "B")	3,661.0	C.Y.
Hot Mix Asphalt, ST, 12.5mm	2,630.0	Ton
18" Reinforced Concrete Pipe, Class III	296.0	L.F.
24" Reinforced Concrete Pipe, Class III	56.0	L.F.
30" Reinforced Concrete Pipe, Class III	80.0	L.F.
18" Reinforced Concrete Pipe, End Section	2	Each
24" Reinforced Concrete Pipe, End Section	2	Each
30" Reinforced Concrete Pipe, End Section	2	Each
58"x36" Reinforced Concrete Arch Pipe, Class III	176.0	L.F.
58"x36" Reinforced Concrete Arch Pipe, End Section	4	Each
10'x4' Precast Concrete Box Culvert	84.0	L.F.
10'x4' Precast Concrete Box Culvert End Section	2	Each
Guardrail, "W" Beam	50.0	L.F.
Guardrail, Bridge End Section, Type "I", Thrie Beam	4	Each
Guardrail, Terminal End Section	4	Each
Roadway Construction Surveying	1.0	L.S.
Barbed Wire Fence, 5 Strands & Metal Post	2,000.0	L.F.
Right-of-Way Markers (Type I)	31	Each
Maintenance of Traffic	Lump Sum	L.S.
Additional Construction Signs	0.0	S.F.

ROADWAY ITEMS (CONTINUED)

4" Wide Thermoplastic Edge Stripe (Continuous White) (60 Mils)	1.135	Mile
4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 Mils)	6,050.0	L.F.
Thermoplastic Legend (White) (120 Mils)	153.0	L.F.
Two-Way Yellow Reflective High Performance Raised Markers	50	Each
Reflectorized Traffic Warning Sign (Encapsulated Lens)	14	Each
Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	3	Each
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4	Each

EROSION CONTROL ITEMS :

Agricultural Limestone	11.0	Ton
Commercial Fertilizer (13-13-13)	5.50	Ton
Ammonium Nitrate	0.55	Ton
Seeding	5.50	Acre
Vegetative Material for Mulch	11.0	Ton
Excelsior Blanket	20,591.0	S.Y.
Temporary Silt Fence (Type I) (AOS 0.15-0.84)	5,107.0	L.F.
Wattles, 20"	1,804.0	L.F.
Loose RipRap (300#)	900.0	Ton

BRIDGE ITEMS :

Bridge Construction Surveying	1.0	L.S.
Test Piles	4	Each
Conventional Static Pile Load Test	0	Each
14" Prestressed Concrete Piling	720.0	L.F.
18" Prestressed Concrete Piling	1,170.0	L.F.
18" Pre-Formed Pile Holes	100.00	L.F.
22" Pre-Formed Pile Holes	100.00	L.F.
Concrete Piling Cut-Off, 14"	100.00	L.F.
Concrete Piling Cut-Off, 18"	100.00	L.F.
Class "A" Bridge Concrete	276.38	C.Y.
40' Prestressed Concrete Beam, Type I + 2	397.50	L.F.
90' Prestressed Concrete Beam, FIB 36"	448.75	L.F.
Reinforcement	38,434.0	Lbs.
Concrete Railing	340.0	L.F.
Loose RipRap (300#)	375.0	Ton
Geotextile Under Riprap, (Type V), (AOS 0.20-0.43)	690.0	S.Y.

NOTICE TO CONTRACTORS:

CONTRACT TIME: 150 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

MINIMUM WAGE RATES for this project have been predetermined by the Secretary of the Department of Labor in accordance with the requirements of Federal regulations governing the expenditure of FEDERAL AID HIGHWAY FUNDS and are set out in the labor regulations contained in the proposal.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Yazoo County, the County Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Robert L. Dixon, County Engineer for Yazoo County, Mississippi, 350 Highland Drive, Yazoo City, MS, 39194. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Yazoo County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Cobie Collins, President
Yazoo County Board of Supervisors