

KEMPER COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Kemper County, Mississippi at the Kemper County Courthouse, DeKalb, Mississippi, until 10:00 a.m. on the 14th day of October, 2019 and shortly thereafter publicly opened for the replacement of deficient bridges with a new structure and approaches – 1@31', 1@60', 4@40', 1@60' AND 1@31' on the Neelytown Road being known as Project No. ERBR-BR-0035(22)B in Kemper County, Mississippi.

CONTRACT TIME: 160 Working Days

BASIS OF AWARD:

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Kemper County and the County Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Terrell W. Temple, Engineer for Kemper County, Mississippi, 1724B 23rd Avenue, Meridian, MS 39301. The cost is twenty-five dollars (\$25.00) for plans and twenty-five dollars (\$25.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Kemper County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

/s/ Johnny Whitsett, President
Kemper County Board of Supervisors

Advert. August 22, 2019
August 29, 2019

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
KEMPER COUNTY BOARD OF SUPERVISORS

SECTION 900 - A

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Kemper County, Mississippi at the Kemper County Courthouse, Dekalb, Mississippi, until 10:00 am on the 14th day of October, 2019 and shortly thereafter publicly opened for the construction of 0.239 miles of PRESTRESSED CONCRETE BEAM SPAN BRIDGE & HMA APPROACHES on the NEELYTOWN ROAD being known as Project No. ERBR-BR-0035(22)B in Kemper County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE (OPPOSITE STATION 10+99.75)	1.000	UN
REMOVAL OF BRIDGE (OPPOSITE STATION 12+91.95)	1.000	UN
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	11,606.000	CY
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B)	1,368.000	CY
SIZE I STABILIZER AGGREGATE, COARSE	70.000	CY
HOT MIX ASPHALT, BASE COURSE (BB-1)	513.000	TON
HOT BITUMINOUS PAVEMENT SURFACE COURSE, (SC-1), (TYPE 8)	188.000	TON
15" REINFORCED CONCRETE PIPE, CLASS III	80.000	LF
GUARD RAIL, W-BEAM	75.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I", THRIE-BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	14.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (90 MIL)	0.481	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (120 MIL)	2,520.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 MIL)	60.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH	20.000	EA

SECTION 900-A
PROJECT NO. ER02R-BR-0035(22)B
KEMPER COUNTY

PERFORMANCE RAISED MARKERS		
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	3.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	1.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	5.620	TON
COMMERCIAL FERTILIZER (13-13-13)	2.810	TON
AMMONIUM NITRATE	0.420	TON
SEEDING	2.810	AC
VEGETATIVE MATERIALS FOR MULCH	5.620	TON
SOLID SODDING	300.000	SY
PORTLAND CEMENT CONCRETE	6.870	CY
PAVED DITCH		
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	2,140.000	LF
WATTLES, 20"	800.000	LF
LOOSE RIPRAP, 200 LB.	200.000	TON

BRIDGE ITEMS:

TEST PILE	3.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	2,945.000	LF
18" PRE-FORMED PILE HOLES	1,200.000	LF
BRIDGE CONCRETE, CLASS "A"	375.330	CY
31' PRESTRESSED CONCRETE BEAM TYPE I & 2	307.500	LF
40' PRESTRESSED CONCRETE BEAM TYPE I & 2	795.000	LF
60' PRESTRESSED CONCRETE BEAM TYPE III	597.500	LF
REINFORCEMENT	67,709.000	LB
CONCRETE RAILING	684.000	LF
LOOSE RIPRAP, 300 LB.	289.000	TON
GEOTEXTILE UNDER 300 LB. RIPRAP, TYPE V, AOS 0.21-0.43	700.000	SY