

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
SCOTT COUNTY BOARD OF SUPERVISORS

SECTION 900 - A

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Scott County, Mississippi at the Scott County Courthouse, Forest, Mississippi, until 10:00 am on the 6th day of May, 2019 and shortly thereafter publicly opened for the construction of 0.120 miles of SITE A & SITE B: PRECAST CONCRETE SPAN BRIDGES WITH HMA APPROACHES on the OLD HILLSBORO ROAD being known as Project No. **ERBR-BR-0062(17)B in Scott County, Mississippi.**

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE STA.108+03 (SITE A)	1.000	UN
REMOVAL OF BRIDGE STA.113+60 (SITE B)	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	338.000	CY
BORROW EXCAVATION) (CONTRACTOR FURNISHED, LVM, CLASS 9)	78.000	CY
EXCESS EXCAVATION (LVM)	150.000	CY
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B)	464.000	CY
HOT MIX ASPHALT, ST 9.5 MM	192.000	TON
HOT MIX ASPHALT, ST. 19 MM	92.000	TON
GUARD RAIL, W-BEAM	350.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I" THRIE-BEAM	8.000	EA
GUARD RAIL, TERMINAL END SECTION	8.000	EA
RIGHT-OF-WAY MARKERS (TYPE II)	8.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MIL)	0.244	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MIL)	0.122	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	337.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	8.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	1.000	EA

SECTION 900 - A
PROJECT NO. ERBR-BR-0062(17)B
SCOTT COUNTY

REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	8.000	EA
---	-------	----

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.440	TON
COMMERCIAL FERTILIZER (13:13:13)	0.220	TON
AMMONIUM NITRATE	0.040	TON
SEEDING	0.220	AC
VEGETATIVE MATERIALS FOR MULCH	0.440	TON
SOLID SODDING	145.000	SY
PORTLAND CEMENT CONCRETE	4.804	CY
PAVED DITCH		
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,150.000	LF
LOOSE RIPRAP, 200 LB.	100.000	TON
WATTLES, 20"	1,400.000	LF

BRIDGE ITEMS:

SITE A ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	720.000	LF
18" PRE-FORMED PILE HOLES	480.000	LF
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	12.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	204.000	LF
31' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
31' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	105.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	272.000	SY

SITE B ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	620.000	LF

SECTION 900 - A
 PROJECT NO. ERBR-BR-0062(17)B
 SCOTT COUNTY

18" PRE-FORMED PILE HOLES	420.000	LF
19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	12.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	138.000	LF
31.33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
31.0' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	98.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	220.000	SY

PROJECT NO. ERBR-STP/BR-0062(17)B
SCOTT COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 110 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Scott County and the County Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction. However, State Aid is not involved in this project.

PLANS AND PROPOSALS may be secured from Kevin C. Thompson, County Engineer for Scott County, Mississippi at 1724-B 23rd Avenue, Meridian. The cost is twenty-five dollars (\$25.00) for plans and twenty-five dollars (\$25.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Jasper County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Johnny P. Harrell, President
Scott County Board of Supervisors