

HUMPHREYS COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Humphreys County, Mississippi at the Humphreys County Courthouse, Belzoni, Mississippi, until 9:00 am on the 6th day of July, 2020 and shortly thereafter publicly opened for the construction of 0.086 miles for BRIDGE REPLACEMENT on the SEVEN MILE ROAD being known as Project No. ERBR-LSBP-27(15) in Humphreys County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
ROADWAY ITEMS:		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF CONCRETE BRIDGE	1.000	UN
@ STA 11 + 65.5		
UNCLASSIFIED EXCAVATION (PM)	708.000	CY
BORROW EXCAVATION (CONTRACTOR FURNISHED, LVM, CLASS 10)	25.000	CY
GRANULAR MATERIAL (LVM), (CLASS 4, GROUP B)	311.000	CY
24" REINFORCED CONCRETE PIPE, CLASS III	112.000	LF
RIGHT-OF-WAY MARKERS (TYPE I)	12.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
EROSION CONTROL ITEMS:		
COMMERCIAL FERTILIZER (13-13-13)	0.580	TON
SEEDING	0.580	AC
VEGETATIVE MATERIALS FOR MULCH	1.160	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)	1,000.000	LF
WATTLES 20"	500.000	LF
BRIDGE ITEMS:		
TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	660.000	LF

31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, 30 Deg SKEW RT. FWD.	12.000	EA
31' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR, 30 Deg SKEW RT. FWD.	6.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 Deg SKEW RT. FWD.	6.000	EA
PRECAST CONCRETE BARRIER RAIL	186.000	LF
38' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, 30 Deg SKEW, RT. FWD.	2.000	EA
38' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, 30 Deg SKEW, RT. FWD.	2.000	EA
11.33' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, (300 LB)	260.500	TN
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21 - 0.43	340.000	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 90 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

MINIMUM WAGE RATES for this project have been predetermined by the Secretary of the Department of Labor in accordance with the requirements of Federal regulations governing the expenditure of FEDERAL AID HIGHWAY FUNDS and are set out in the labor regulations contained in the proposal.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Humphreys County, the County Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from J. Wayne Morrison, County Engineer for Humphreys County, Mississippi, P. O. Box 567, Yazoo City. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Humphreys County accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Richard Stephens, President
Humphreys County Board of Supervisors