

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
WILKINSON COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Wilkinson County, Mississippi at the Wilkinson County Courthouse, Woodville, Mississippi, until 10:00 am on the 24th day of June, 2019 and shortly thereafter publicly opened for the construction of 0.157 miles of BOX BRIDGE AND APPROACHES on the PERRYTOWN ROAD being known as Project No. ERBR-STP-1184(6)B in Wilkinson County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

<u>ITEM</u>	<u>QUANTITY</u>	<u>UNIT</u>
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE (STA. 288+89.00)	1.000	UN
REMOVAL OF PAVEMENT (ALL DEPTHS)	320.000	SY
UNCLASSIFIED EXCAVATION (FM)	794.000	CY
BORROW EXCAVATION (F.M.E.)	308.000	CY
(CONTRACTOR FURNISHED) (CLASS 9)		
SURPLUS EXCAVATION (FM)	424.000	CY
STRUCTURE EXCAVATION	1,196.000	CY
GRANULAR MATERIAL (LVM),	526.000	CY
(CLASS 4, GROUP B)		
HOT MIX ASPHALT, (TYPE ST) (9.5mm)	225.000	TON
COLD MILLING OF BITUMINOUS	44.000	SY
PAVEMENT, ALL DEPTHS		
ASPHALT FOR PRIME COAT (EA-1)	593.000	GAL
RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
CONSTRUCTION AND REMOVAL OF	LUMP SUM	LS
DIVERSION BRIDGE		
CONSTRUCTION AND REMOVAL OF DETOUR	LUMP SUM	LS
ROAD		
4" WIDE TEMPORARY TRAFFIC STRIPE	617.000	LF
4" WIDE THERMOPLASTIC EDGE STRIPE	0.316	MI
(CONTINUOUS WHITE) (60 MIL)		
4" WIDE THERMOPLASTIC TRAFFIC	1,669.000	LF
STRIPE (CONTINUOUS YELLOW) (90 MIL		
TEMPORARY STREAM DIVERSION	1.000	EA

PROJECT NO. ERBR-STP-1184(6)B
WILKINSON COUNTY

EROSION CONTROL ITEMS:

COMMERCIAL FERTILIZER (13-13-13)	0.300	TON
AMMONIUM NITRATE	0.100	
TON		
SEEDING	1.010	AC
VEGETATIVE MATERIALS FOR MULCH	2.020	TON
SOLID SODDING	100.000	SY
TEMPORARY SILT FENCE	1,457.000	LF
(TYPE I OR II) (AOS .15-.84)		
LOOSE RIPRAP, 200 LB.	89.000	TON
GEOTEXTILE UNDER RIPRAP,	170.000	SY
TYPE V, AOS 0.21-0.43		
WATTLES 20"	150.000	LF

BOX BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"	402.780	CY
REINFORCEMENT	66,127.000	LB

PROJECT NO. ERBR-STP-1184(6)B
WILKINSON COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 90 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND PROPOSALS may be secured from J. A. Marlow, Jr., County Engineer for Wilkinson County, Mississippi, P. O. Box 1267, Natchez. The Cost is one hundred dollars (\$100.00) for plans and dollars (\$0.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Wilkinson County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Kenyon Jackson, President
Wilkinson County Board of Supervisors