



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Coahoma
Project No. LSBP-14(10)
Road Name. Rudyard Jonestown Road

BIDS RECEIVED: WEDNESDAY, MARCH 12, 2025 AT 10:00 AM IN THE BOARDROOM AT CLARKSDALE, MS

Project Description: 0.052 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE (6+23)	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	80.000	LF
UNCLASSIFIED EXCAVATION (FM)	116.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	56.000	CY
CHANNEL EXCAVATION (FM)	331.000	CY
CRUSHED STONE, NO. 610	451.000	TON
18" POLYMERIC COATED CORRUGATED METAL PIPE, 14 GAGE, 2-2/3" x 1/2" CORRUGATION	120.000	LF
36" POLYMERIC COATED CORRUGATED METAL PIPE, 14 GAGE, 3" x 1" CORRUGATION	60.000	LF
36" POLYMERIC COATED CORRUGATED METAL END SECTION, 14 GAGE	2.000	EA
RIGHT-OF-WAY MARKERS (TYPE II)	7.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.800	TON
COMMERCIAL FERTILIZER (13:13:13)	0.400	TON
SEEDING	0.400	AC
VEGETATIVE MATERIALS FOR MULCH	1.200	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	540.000	LF
WATTLES, 20"	100.000	LF
LOOSE RIPRAP, 300 LB.	65.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS < 0.43	140.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" STEEL PILING	980.000	LF
18" PRE-FORMED PILE HOLES	200.000	LF
BRIDGE CONCRETE, CLASS A	54.000	CY
REINFORCEMENT	8,628.000	LB
19 ' PRECAST CONCRETE SLAB UNIT, 3.5" INTERIOR	8.000	EA
19 ' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	4.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	4.000	EA

31 ' PRECAST CONCRETE SLAB UNIT, 4.5 ' INTERIOR	2.000	EA
19 ' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	138.000	LF
LOOSE RIPRAP, 300 LB.	160.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS < 0.43	321.000	SY