



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS

County Covington
Project No. LSBP-16(24)
Road Name. Pearce Road

BIDS RECEIVED: 10:00 AM February 3, 2025 at the Chancery Building in Collins MS

Project Description: 0.075 miles of BOX BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 31+46	1.000	UN
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	3,800.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (LVM), (CLASS 5, GROUP C)	700.000	CY
RIGHT-OF-WAY MARKERS (TYPE I)	12.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	2.800	TON
COMMERCIAL FERTILIZER (13-13-13)	1.400	TON
AMMONIUM NITRATE	0.280	TON
SEEDING	1.400	AC
VEGETATIVE MATERIALS FOR MULCH	1.400	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)	1,100.000	LF
WATTLES, 20" DIAMETER	200.000	LF
LOOSE RIPRAP, 200 LB.	150.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS < 0.43, NON-WOVEN	276.000	SY

BOX BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS BB	401.330	CY
REINFORCEMENT	75,129.000	LB