



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Hinds
Project No. LSBP-25(53)
Road Name. Snake Creek Road

BIDS RECEIVED: 10:00 AM, August 14, 2024 County Board Room Jackson MS

Project Description: 0.052 miles of BOX CULVERT & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST CONCRETE BRIDGE STA. 12+99.81	1.000	UN
REMOVAL OF ASPHALT PAVEMENT (ALL DEPTHS)	541.000	SY
REMOVAL OF PIPE (ALL SIZES)	24.000	LF
UNCLASSIFIED EXCAVATION (FM)	625.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	2,162.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (FM OR LVM), (CLASS 5, GROUP B)	301.000	CY
CLASS "B" STRUCTURAL CONCRETE	203.230	CY
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	1.854	CY
REINFORCING STEEL	37,532.000	LB
18" REINFORCED CONCRETE PIPE, CLASS III	65.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	11.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.820	TON
COMMERCIAL FERTILIZER (13:13:13)	0.410	TON
SEEDING	0.410	AC
VEGETATIVE MATERIALS FOR MULCH	0.820	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	600.000	LF
WATTLES, 20" DIAMETER	200.000	LF
LOOSE RIPRAP, 300 LB.	198.000	TON
GEOTEXTILE FABRIC UNDER RIPRAP, TYPE V, AOS (0.21-0.43)	365.000	SY