



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

**County** Hinds  
**Project No.** LSBP-25(55)  
**Road Name.** Parson Road

**BIDS RECEIVED:** Wednesday, APRIL 16, 2025, In the County Boardroom at Jackson, Ms  
**Project Description:** 0.057 miles of BOX BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST CONCRETE BRIDGE @ STA. 12+99.81	1.000	UN
REMOVAL OF ASPHALT PAVEMENT	667.000	SY
REMOVAL OF PIPE (ALL SIZES)	64.000	LF
UNCLASSIFIED EXCAVATION (FM)	600.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9 )	3,806.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (LVM), (CLASS 5, GROUP B )	311.000	CY
18 " REINFORCED CONCRETE PIPE, CLASS III	38.000	LF
24 " REINFORCED CONCRETE PIPE, CLASS III	78.000	LF
18 " REINFORCED CONCRETE PIPE, END SECTION	1.000	EA
24" REINFORCED CONCRETE PIPE, END SECTION	3.000	EA
18" BRANCH CONNECTION FOR RCP TO WING WALL OF BOX	1.000	EA
24 " BRANCH CONNECTION FOR RCP TO WING WALL OF BOX	1.000	EA
RIGHT-OF-WAY MARKERS (TYPE II )	12.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.200	TON
COMMERCIAL FERTILIZER ( 13:13:13 )	0.600	TON
SEEDING	0.410	AC
VEGETATIVE MATERIALS FOR MULCH	1.200	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II ) (AOS 0.15-0.84 )	900.000	LF
WATTLES, 20"	200.000	LF
LOOSE RIPRAP, 300 LB.	124.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS <0.43, NON-WOVEN	230.000	SY

BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS BB	174.160	CY
REINFORCEMENT	35,357.000	LB