



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Hinds
Project No. LSBP-25(56)
Road Name. Rockett Road

BIDS RECEIVED: WEDNESDAY, APRIL 16, 2025 AT 10:00 AM IN THE BOARDROOM AT JACKSON, MS

Project Description: 0.099 miles of BOX BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRE-CAST CONCRETE @ STA. 12+99.53	1.000	UN
REMOVAL OF ASPHALT PAVEMENT	1,167.000	SY
REMOVAL OF PIPE (ALL SIZES)	139.000	LF
UNCLASSIFIED EXCAVATION (FM)	1,298.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	895.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (LVM), (CLASS 5, GROUP B)	474.000	CY
18 " CORRUGATED POLYETHYLENE PIPE	12.000	LF
24 " CORRUGATED POLYETHYLENE PIPE	81.000	LF
30 " CORRUGATED POLYETHYLENE PIPE	80.000	LF
18 " CORRUGATED POLYETHYLENE PIPE, END SECTION	1.000	EA
24 " CORRUGATED POLYETHYLENE PIPE, END SECTION	1.000	EA
30 " CORRUGATED POLYETHYLENE PIPE, END SECTION	1.000	EA
24 " BRANCH CONNECTION INTO BOX BRIDGE WING WALL	1.000	EA
30 " BRANCH CONNECTION INTO BOX BRIDGE WING WALL	1.000	EA
RIGHT-OF-WAY MARKERS (TYPE II)	12.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.800	TON
COMMERCIAL FERTILIZER (13:13:13)	0.400	TON
SEEDING	0.400	AC
VEGETATIVE MATERIALS FOR MULCH	0.800	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)	900.000	LF
WATTLES, 20"	200.000	LF
LOOSE RIPRAP, 300 LB.	101.000	TON
GEOTEXTILE UNDER RIP RAP TYPE V, AOS < 0.43, NON-WOVEN	187.000	SY

BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS BB	212.180	CY
REINFORCEMENT	40,449.000	LB