



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Itawamba
Project No. LSBP-29(37)
Road Name. Chester Shumpert Road

BIDS RECEIVED: 10:00AM Thursday, March 12, 2025 at the Boardroom in Fulton MS

Project Description: 0.128 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF EXISTING BRIDGE AT STA. 22+38.97	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	112.000	LF
UNCLASSIFIED EXCAVATION (FM)	1,313.000	CY
BORROW EXCAVATION (FME)	100.000	CY
EXCESS EXCAVATION (LVM)	614.000	CY
GEOTEXTILE FABRIC STABILIZATION (TYPE V) (AOS <0.43) (NON-WOVEN)	2,091.000	SY
CRUSHED STONE (3/4" & DOWN) (LVM)	406.000	CY
18" CORRUGATED POLYETHYLENE PIPE	112.000	LF
RIGHT-OF-WAY MARKERS (TYPE I)	10.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.750	TON
COMMERCIAL FERTILIZER (13-13-13)	0.380	TON
AMMONIUM NITRATE	0.190	TON
SEEDING	0.750	AC
SOLID SODDING	100.000	SY
EXCELSIOR BLANKET	1,078.000	SY
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	790.000	LF
WATTLES, 20"	240.000	LF
LOOSE RIPRAP, 200 LB.	159.000	TON
GEOTEXTILE UNDER RIPRAP (TYPE V, NON-WOVEN) (AOS >0.43)	161.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
18" CONCRETE PILING	600.000	LF
24" PRE-FORMED PILE HOLES	414.000	LF
BRIDGE CONCRETE, CLASS A	47.000	CY
REINFORCEMENT	8,672.000	LB
19 ' PRECAST CONCRETE SLAB UNIT, 3.2' INTERIOR	12.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA

19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	156.000	LF
LOOSE RIPRAP, 300 LB.	310.000	TON
GEOTEXTILE UNDER RIPRAP (TYPE V, NON-WOVEN) (AOS <0.43)	340.000	SY