



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Jones
Project No. LSBP-34(28)
Road Name. Norton Road

BIDS RECEIVED: Thursday, April 24, 2025 in the Courthouse at Laurel, MS

Project Description: 0.074 miles of BOX BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF OBSTRUCTIONS	1.000	LS
REMOVAL OF PRECAST BRIDGE STA. 11+90.41	1.000	UN
REMOVAL OF PAVEMENT (ASPHALT)	762.000	SY
REMOVAL OF PIPE (ALL SIZES)	37.000	LF
UNCLASSIFIED EXCAVATION (FM)	477.000	CY
MUCK EXCAVATION (FM)	257.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	555.000	CY
EXCESS EXCAVATION (LVM)	340.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
CRUSHED STONE (SIZE 825)	470.000	TON
FILTER MATERIAL FOR FILTER BEDS, TYPE "A"	463.000	TON
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	2.000	TON
COMMERCIAL FERTILIZER (13:13:13)	1.000	TON
AMMONIUM NITRATE	0.100	TON
SEEDING	1.000	AC
VEGETATIVE MATERIALS FOR MULCH	2.000	TON
SOLID SODDING	100.000	SY
TEMPORARY GRASSING	1.000	AC
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	888.000	LF
WATTLES, 12"	200.000	LF
LOOSE RIPRAP, 200 LB.	204.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS < 0.43	378.000	SY

BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"	197.190	CY
REINFORCEMENT	35,179.000	LB