



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS

County Lauderdale
Project No. LSBP-38(40)
Road Name. RICHARD JOHNSON

BIDS RECEIVED: Thursday July 25th, 2024 Supervisor's Boardroom at Meridian, MS
Project Description: 0.047 miles of BOX BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE AT STA. 18+10.97	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	320.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	500.000	CY
EXCESS EXCAVATION (FM)	730.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B)	219.000	CY
SIZE I STABILIZER AGGREGATE, COARSE	55.000	CY
CLASS "C" STRUCTURAL CONCRETE	30.000	CY
RIGHT-OF-WAY MARKERS (TYPE II)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

SOLID SODDING	150.000	SY
EXCELSIOR BLANKET	450.000	SY
HYDROSEEDING	0.400	AC
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	500.000	LF
WATTLES, 20 in	100.000	LF
LOOSE RIPRAP, 200 LB.	100.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS < 0.43, NON-WOVEN	230.000	SY

BOX BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS BB	140.600	CY
REINFORCEMENT	28,057.000	LB