



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

**County** Lee  
**Project No.** LSBP-41(38)  
**Road Name.** Fellowship Road

**BIDS RECEIVED:** MONDAY, MARCH 31, 2025 AT 10:00 AM IN THE BOARDROOM AT TUPELO, MS

**Project Description:** 0.041 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF Existing Bridge At Sta. 317+46	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	161.000	CY
BORROW EXCAVATION (FME) (CONTRACTOR FURNISHED) (CLASS 9-6)	73.000	CY
EXCESS EXCAVATION (LVM)	262.000	CY
GEOTEXTILE FABRIC STABILIZATION (TYPE V) (AOS<0.43) (NON-WOVEN)	657.000	SY
CRUSHED STONE SIZE (3/4" Down) (LVM)	172.000	CY
RIGHT-OF-WAY MARKERS (TYPE I)	9.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	1.000	EA
LOOSE RIPRAP, 300 LB.	85.000	TON
GEOTEXTILE UNDER RIPRAP , TYPE V, NON-WOVEN, AOS < 0.43	75.000	SY

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.140	TON
COMMERCIAL FERTILIZER (13-13-13)	0.070	TON
SEEDING	0.140	AC
VEGETATIVE MATERIAL FOR MULCH	0.270	TON
SOLID SODDING	100.000	SY
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	400.000	LF
WATTLES, 20"	100.000	LF

STA. 372+45.00 - 1 @ 19', 1 @ 40', 1 @ 19' PRECAST CONCRETE SPANS

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
18" CONCRETE PILING	600.000	LF
24" PREFORMED PILE HOLES	412.560	LF
BRIDGE CONCRETE, CLASS A	46.680	CY
REINFORCEMENT	8,672.000	LB
19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	12.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA

PRECAST CONCRETE BARRIER RAIL	156.000	LF
LOOSE RIPRAP, 300 LB.	303.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS<0.43	326.000	SY