



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Lincoln
Project No. LSBP-43(52)
Road Name. BETHEL ROAD SE

BIDS RECEIVED: TUESDAY, JANUARY 7, 2025 AT 10:00 AM IN THE BOARDROOM AT BROOKHAVEN, MS

Project Description: 0.199 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ 15+10.96	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	105.000	LF
UNCLASSIFIED EXCAVATION (FM)	5,705.000	CY
BORROW EXCAVATION (CONTRACTOR FURNISHED LVM, CLASS 7-5)	600.000	CY
CHANNEL EXCAVATION (FM)	775.000	CY
EXCESS EXCAVATION (FM)	2,162.000	CY
GRANULAR MATERIAL (LVM), (CLASS 4, GROUP B)	1,600.000	CY
18" REINFORCED CONCRETE PIPE, CLASS III	184.000	LF
44" X 27" REINFORCED CONCRETE ARCH PIPE, CLASS III	56.000	LF
44" X 27" REINFORCED CONCRETE ARCH PIPE, END SECTION	2.000	EA
FILTER MATERIAL FOR FILTER BEDS, TYPE A	78.000	TON
RIGHT-OF-WAY MARKERS (TYPE II)	26.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

COMMERCIAL FERTILIZER (13-13-13)	2.980	TON
SEEDING	2.980	AC
VEGETATIVE MATERIALS FOR MULCH	8.940	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	2,100.000	LF
WATTLES, 20"	700.000	LF
LOOSE RIPRAP, 300 LB.	763.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V NON-WOVEN, AOS < 0.21-0.43	1,173.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	1,350.000	LF
18" PRE-FORMED PILE HOLES	360.000	LF
BRIDGE CONCRETE, CLASS "A"	171.000	CY
31' PRESTRESSED CONCRETE BEAM TYPE I+2	307.500	LF
80' PRESTRESSED CONCRETE BEAM TYPE III	398.750	LF

REINFORCEMENT	29,331.000	LB
CONCRETE RAILING	284.000	LF
LOOSE RIPRAP, 300 LB.	700.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V NON-WOVEN, AOS < 0.21-0.43	800.000	SY