



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Monroe
Project No. LSBP-48(26)
Road Name. Tumbikbe Road

BIDS RECEIVED: Monday, August 5, 2024 9:00 a.m. in the Board Room at Aberdeen, MS

Project Description: 0.104 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF EXISTING BRIDGE AT STA. 41+75	1.000	UN
REMOVAL OF PAVEMENT (ALL DEPTHS)	1,076.000	SY
UNCLASSIFIED EXCAVATION (FM)	1,007.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9-6)	325.000	CY
GEOTEXTILE FABRIC STABILIZATION (TYPE V) (AOS <0.43)	1,742.000	SY
CRUSHED STONE (SIZE 3/4" & DOWN) (FM)	341.000	CY
18in REINFORCED CONCRETE PIPE, CLASS III	40.000	LF
BRIDGE CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	4.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.600	TON
COMMERCIAL FERTILIZER (13-13-13)	0.800	TON
SEEDING	0.800	AC
VEGETATIVE MATERIALS FOR MULCH	2.400	TON
SOLID SODDING	100.000	SY
EXCELSIOR BLANKET	127.000	SY
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	1,150.000	LF
WATTLES, 20"	100.000	LF
LOOSE RIPRAP, 300 LB.	75.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V NON-WOVEN, AOS <0.43	75.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" STEEL PILING	880.000	LF
18" PRE-FORMED PILE HOLES	688.000	LF
BRIDGE CONCRETE, CLASS A	7.420	CY
REINFORCEMENT	141.000	LB
31' PRECAST CONCRETE SLAB UNIT, 3.5 INTERIOR	12.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5 INTERIOR	6.000	EA

31' PRECAST CONCRETE SLAB UNIT, 3.5 EXTERIOR	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5 EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	204.000	LF
31.33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, STEEL PILE	2.000	EA
31.00' PRECAST CONCRETE CAP, END UNIT, STEEL PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	463.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V NON-WOVEN, AOS <0.43	410.000	SY