



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Prentiss
Project No. LSBP-59(32)
Road Name. County Road 5250

BIDS RECEIVED: County Board Room, Boonville MS, 10:00 AM, July 17, 2024

Project Description: 0.104 miles of BRIDGE & APPROACHES Precast Concrete Span Bridge & Approaches to replace BR. NO. 147

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF EXISTING BRIDGE AT STA. 21+82.98	1.000	UN
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	1,292.000	CY
GEOTEXTILE FABRIC STABILIZATION (TYPE V) (AOS <0.43)	1,643.000	SY
CRUSHED STONE SIZE (3/4" & DOWN) (FM)	315.000	CY
RIGHT-OF-WAY MARKERS (TYPE I)	12.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	2.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.500	TON
COMMERCIAL FERTILIZER (13-13-13)	0.300	TON
AMMONIUM NITRATE	0.100	TON
SEEDING	1.000	AC
SOLID SODDING	100.000	SY
EXCELSIOR BLANKET	250.000	SY
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	1,600.000	LF
WATTLES, 20"	100.000	LF
LOOSE RIPRAP, 300 LB.	150.000	TON
GEOTEXTILE UNDER RIPRAP, (TYPE V) (NON-WOVEN), (AOS <0.43)	150.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
12" STEEL PILING	800.000	LF
18" PRE-FORMED PILE HOLES	505.000	LF
BRIDGE CONCRETE, CLASS "B"	10.230	CY
REINFORCEMENT	457.000	LB
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	12.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	204.000	LF

31.33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, STEEL PILE	2.000	EA
31.0' PRECAST CONCRETE CAP, END UNIT, STEEL PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	332.000	TON
GEOTEXTILE UNDER RIPRAP, (TYPE V NON-WOVEN), AOS <0.43	295.000	SY