



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Prentiss
Project No. LSBP-59(33)
Road Name. County Road 1150

BIDS RECEIVED: MONDAY, MAY 5, 2025 AT 10:00 AM IN THE BOARDROOM AT BOONEVILLE, MS

Project Description: 0.199 miles of BRIDGE & APPROACHES Prestress Concrete Bridge and Approaches to replace BR. NO. 15

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF EXISTING BRIDGE AT STA. 30+92.04	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	72.000	LF
UNCLASSIFIED EXCAVATION (PM)	1,058.000	CY
BORROW EXCAVATION (FME) (CONTRACTOR FURNISHED) (CLASS 9-6)	4,745.000	CY
EXCESS EXCAVATION (FM)	578.000	CY
GEOTEXTILE FABRIC STABILIZATION (TYPE V) (AOS < 0.43)	3,265.000	SY
GRANULAR MATERIAL (LVM), (CLASS 5, GROUP "C")	869.000	CY
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	0.752	CY
72" REINFORCED CONCRETE PIPE, CLASS III	80.000	LF
72" REINFORCED CONCRETE PIPE, END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.250	TON
COMMERCIAL FERTILIZER (13-13-13)	0.630	TON
SEEDING	1.250	AC
VEGETATIVE MATERIALS FOR MULCH	3.750	TON
SOLID SODDING	100.000	SY
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	2,000.000	LF
WATTLES, 20"	500.000	LF
LOOSE RIPRAP, 200 LBS.	120.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS < 0.43 (Non-Woven)	140.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" STEEL PILING	1,350.000	LF
18" PRE-FORMED PILE HOLE	1,098.000	LF
BRIDGE CONCRETE, CLASS "A"	227.000	CY
40' PRESTRESSED CONCRETE BEAM, TYPE I+ II	397.500	LF
80' PRESTRESSED CONCRETE BEAM, TYPE III	398.750	LF

REINFORCEMENT	35,777.000	LB
CONCRETE RAILING	320.000	LF
LOOSE RIPRAP, 300 LBS.	704.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS < 0.43 (Non-Woven)	685.000	SY