



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Sharkey
Project No. LSBP-63(18)
Road Name. Box Estate Road

BIDS RECEIVED: Boardroom, Rolling Fork MS, 10:00AM, Tuesday, February 25th 2025

Project Description: 0.104 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE (10+94)	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	991.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	426.000	CY
CHANNEL EXCAVATION (FM)	426.000	CY
CRUSHED STONE 825 B	556.000	TON
RIGHT-OF-WAY MARKERS (TYPE II)	9.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	2.200	TON
COMMERCIAL FERTILIZER (13:13:13)	1.100	TON
SEEDING	1.100	AC
VEGETATIVE MATERIALS FOR MULCH	3.300	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,130.000	LF
WATTLES, 20"	100.000	LF
LOOSE RIPRAP, 300 LB.	90.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS<0.43	167.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14 " PRESTRESSED CONCRETE PILING	1,010.000	LF
18" PRE-FORMED PILE HOLES	200.000	LF
31 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR 30 DEGREE SKEW, RT. FWD	12.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 4.5 ' INTERIOR, 30 DEGREE SKEW, RT. FWD.	6.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEGREE SKEW, RT. FWD.	6.000	EA
PRECAST CONCRETE BARRIER RAIL	186.000	LF
38.0 ' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,30 DEG SKEW, RT. FWD.	2.000	EA
38.0 ' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, 30 DEG SKEW, RT. FWD.	2.000	EA
11.33' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	274.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS<0.43	537.000	SY