



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Smith

Project No. LSBP-65(28)

Road Name. SMITH COUNTY ROAD 146

BIDS RECEIVED: FRIDAY, MAY 16, 2025 AT 10:00 AM IN THE CHANCERY BUILDING AT RALEIGH, MS

Project Description: 0.169 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF STEEL GIRDER BRIDGE AT STA. 25+56.00	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	40.000	LF
UNCLASSIFIED EXCAVATION (FM)	1,874.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	500.000	CY
EXCESS EXCAVATION (FM)	968.000	CY
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B)	610.000	CY
CRUSHED STONE (SIZE 610) (LVM)	184.000	CY
SIZE I STABILIZER AGGREGATE, COARSE	83.000	CY
RIGHT-OF-WAY MARKERS (TYPE II)	14.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	8.000	EA

EROSION CONTROL ITEMS:

SOLID SODDING	150.000	SY
HYDROSEEDING	0.900	AC
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,500.000	LF
WATTLES, 20"	200.000	LF
LOOSE RIPRAP, 200 LB.	150.000	TON
LOOSE RIPRAP, 300 LB.	140.000	TON
GEOTEXTILE UNDER RIPRAP, (TYPE V)(AOS <0.43) (NON-WOVEN)	340.000	SY

BRIDGE "A"

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14 " PRESTRESSED CONCRETE PILING	1,035.000	LF
18" PRE-FORMED PILE HOLES	900.000	LF
40' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	24.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR	8.000	EA
PRECAST CONCRETE BARRIER RAIL	320.000	LF
31.17 ' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,	3.000	EA
31.17 ' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.17 ' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	210.000	TON

GEOTEXTILE UNDER RIPRAP, (TYPE V) (AOS <0.43) (NON-WOVEN)	510.000	SY
<u>BRIDGE "B"</u>		
TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14 " PRESTRESSED CONCRETE PILING	630.000	LF
18 " PRE-FORMED PILE HOLES	500.000	LF
31 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	18.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	186.000	LF
31.0 ' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,	2.000	EA
31.0 ' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE,	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	190.000	TON
GEOTEXTILE UNDER RIPRAP, (TYPE V) (AOS <0.43) (NON-WOVEN)	450.000	SY