



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Tippah
Project No. LSBP-70(29)
Road Name. County Road 427

BIDS RECEIVED: MONDAY, APRIL 7, 2025 AT 10:00 AM IN THE BOARDROOM AT RIPLEY, MS

Project Description: 0.151 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF EXISTING BRIDGE AT STA. 29+80.48	1.000	UN
REMOVAL OF GROUTED RIPRAP	124.000	SY
REMOVAL OF EXISTING PIPE (ALL SIZES)	95.000	LF
REMOVE AND RELAY RIPRAP	530.000	SY
UNCLASSIFIED EXCAVATION (FM)	734.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	1,093.000	CY
EXCESS EXCAVATION (FM)	1,315.000	CY
GEOTEXTILE FABRIC STABILIZATION (TYPE V, NON-WOVEN) (AOS < 0.43)	2,294.000	SY
GRANULAR MATERIAL (LVM), (CLASS 5, GROUP "C")	477.000	CY
48" REINFORCED CONCRETE PIPE, CLASS III	40.000	LF
48" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
18" CORRUGATED POLYETHYLENE PIPE	103.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.780	TON
COMMERCIAL FERTILIZER (13-13-13)	0.390	TON
AMMONIUM NITRATE	0.200	TON
SEEDING	0.780	AC
VEGETATIVE MATERIALS FOR MULCH	2.340	TON
SOLID SODDING	100.000	SY
EXCELSIOR BLANKET	1,976.000	SY
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	560.000	LF
WATTLES, 20"	260.000	LF
LOOSE RIPRAP, 200 LB.	90.000	TON
LOOSE RIPRAP, 300 LB.	120.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS <0.43, NON-WOVEN	208.000	SY

BRIDGE ITEMS STA. 29+70, 1 @ 40', 1 @ 80', 1 @ 40' PRESTRESSED CONCRETE BEAM SPAN BRIDGE, 30° RT. FWD

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA

14" STEEL PILING	1,710.000	LF
18" PRE-FORMED PILE HOLE	1,162.440	LF
BRIDGE CONCRETE, CLASS A	234.400	CY
40 Ft. PRESTRESSED CONCRETE BEAM, TYPE I + 2	397.500	LF
80 Ft. PRESTRESSED CONCRETE BEAM TYPE III	398.750	LF
REINFORCEMENT	37,960.170	LB
CONCRETE RAILING	318.840	LF
LOOSE RIPRAP, 300 LB.	225.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS <0.43	826.000	SY