



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

**County** Washington  
**Project No.** LSBP-76(29)  
**Road Name.** HANDLEY ROAD

**BIDS RECEIVED:** THURSDAY, APRIL 24, 2025 AT 10:00 AM IN THE BOARDROOM AT GREENVILLE, MS

**Project Description:** 0.047 miles of BRIDGE & APPROACHES

**Roadway Items:**

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE (10+34)	1.000	UN
REMOVAL OF ASPHALT PAVEMENT	146.000	SY
UNCLASSIFIED EXCAVATION (FM)	22.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9 )	7.000	CY
CHANNEL EXCAVATION (FM)	256.000	CY
CRUSHED STONE , 825 B	120.000	TON
RIGHT-OF-WAY MARKERS (TYPE II)	6.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3 )	4.000	EA

**EROSION CONTROL ITEMS:**

AGRICULTURAL LIMESTONE	0.600	TON
COMMERCIAL FERTILIZER ( 13:13:13 )	0.300	TON
SEEDING	0.300	AC
VEGETATIVE MATERIALS FOR MULCH	0.900	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)	380.000	LF
WATTLES, 20"	100.000	LF

**BRIDGE ITEMS:**

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
18 " PRESTRESSED CONCRETE PILING	2,000.000	LF
22" PRE-FORMED PILE HOLES	520.000	LF
BRIDGE CONCRETE, CLASS A	91.000	CY
REINFORCEMENT	16,377.000	LB
31' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	24.000	EA
31' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	12.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	12.000	EA
PRECAST CONCRETE BARRIER RAIL	372.000	LF
LOOSE RIPRAP, 300 LB.	295.000	TON
GEOTEXTILE FABRIC UNDER RIPRAP, TYPE V, NON-WOVEN, AOS <0.43	571.000	SY