



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Washington
Project No. LSBP-76(31)
Road Name. BURDETT ROAD

BIDS RECEIVED: Thursday, April 24, 2025 in the Boardroom at Greenville, MS

Project Description: 0.08 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE (14+96)	1.000	UN
REMOVAL OF PAVEMENT	528.000	SY
REMOVAL OF PIPE (ALL SIZES)	43.000	LF
UNCLASSIFIED EXCAVATION (FM)	147.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	318.000	CY
CHANNEL EXCAVATION (FM)	635.000	CY
CRUSHED STONE, 825 B	443.000	TON
24" POLYMERIC COATED CORRUGATED METAL PIPE, 14 GAGE, 2-2/3" CORRUGATION	40.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	7.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.200	TON
COMMERCIAL FERTILIZER (13:13:13)	0.600	TON
SEEDING	0.600	AC
VEGETATIVE MATERIALS FOR MULCH	1.800	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)	735.000	LF
WATTLES, 20"	200.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
18 " PRESTRESSED CONCRETE PILING	1,310.000	LF
22" PRE-FORMED PILE HOLES	360.000	LF
BRIDGE CONCRETE, CLASS A	62.000	CY
REINFORCEMENT	11,125.000	LB
19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	4.000	EA
19' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	2.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	12.000	EA
31' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	6.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	6.000	EA

PRECAST CONCRETE BARRIER RAIL	224.000	LF
LOOSE RIPRAP, 300 LB.	317.000	TON
GEOTEXTILE FABRIC UNDER RIPRAP, TYPE V, AOS<0.43	615.000	SY