



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

**County** Wilkinson  
**Project No.** LSBP-79(29)  
**Road Name.** WHETSTONE ROAD

**BIDS RECEIVED:** Tuesday, December 10, 2024@10:00am in Boardroom Woodville MS

**Project Description:** 0.144 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 12+69.72	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	40.000	LF
UNCLASSIFIED EXCAVATION (FM)	3,184.000	CY
CHANNEL EXCAVATION (FM)	330.000	CY
EXCESS EXCAVATION (FM)	2,668.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	1,108.000	CY
RIGHT-OF-WAY MARKERS (TYPE II)	15.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

COMMERCIAL FERTILIZER (13-13-13)	1.980	TON
SEEDING	1.980	AC
VEGETATIVE MATERIALS FOR MULCH	5.940	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,800.000	LF
WATTLES, 20 INCH	260.000	LF
LOOSE RIPRAP, 300 LB.	1,000.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V NON-WOVEN, AOS 0.21-0.43	1,006.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	2,070.000	LF
18" PRE-FORMED PILE HOLES	360.000	LF
BRIDGE CONCRETE, CLASS "A"	154.000	CY
31' PRESTRESSED CONCRETE BEAM, TYPE I+2	307.500	LF
60' PRESTRESSED CONCRETE BEAM, TYPE III	298.750	LF
REINFORCEMENT	26,111.000	LB
CONCRETE RAILING	244.000	LF
LOOSE RIPRAP, 300 LB.	560.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V NON-WAVEN, AOS 0.21-0.43	577.000	SY

ALTERNATE #1

CRUSHED STONE 610, (LVM)

1,000.000

CY

ALTERNATE #2

EROSION MAT

400.000

SY