



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Amite
Project No.	SABP-03(01)
Road Name.	P.P. WILSON ROAD

BIDS RECEIVED: MONDAY, JANUARY 26, 2026 AT 10:00 AM IN THE BOARDROOM AT LIBERTY, MS

Project Description: 0.094 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Precast Concrete Bridge (Sta. 121+12.00)	1.000	UN
Borrow Excavation (Contractor Furnished, FME Class 9)	536.000	CY
Channel Excavation (F.M.)	200.000	CY
Granular Material (L.V.M.) (Class 5, Group "C")	1,714.000	CY
Crushed Stone, Size 610 (F.M.)	64.000	CY
Hot Mix Asphalt, ST, 9.5 mm	176.000	TON
Guardrail, W-Beam	75.000	LF
Guardrail, Bridge End Section, Type "I" Thrie-Beam	4.000	EA
Guardrail, Terminal End Section	4.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4"-Wide Thermoplastic Edge Stripe (Continuous White) (60 mil)	0.189	MI
4"-Wide Thermoplastic Traffic Stripe (Skip Yellow) (90 mil)	0.095	MI
Two Way Yellow Reflective High Performance Raised Markers	8.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:

Agricultural Limestone	1.400	TON
Commercial Fertilizer (13-13-13)	0.210	TON
Seeding	0.700	AC
Vegetative Materials for Mulch	1.400	TON
Solid Sodding	68.000	SY
Excelsior Blanket	400.000	SY
Temporary Silt Fence (Type II) (AOS 0.15 - 0.84)	1,200.000	LF
Wattles, 20"	160.000	LF

BRIDGE ITEMS:

Test Piles	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14" Prestressed Concrete Piling	680.000	LF
18" Preformed Pile Holes	200.000	LF
Bridge Concrete, Class "B"	4.990	CY

Reinforcement	596.000	LB
31' Precast Concrete Slab Unit, 3.5' Interior	12.000	EA
40' Precast Concrete Slab Unit, 3.5' Interior	6.000	EA
31' Precast Concrete Slab Unit, 3.5' Exterior	4.000	EA
40' Precast Concrete Slab Unit, 3.5' Exterior	2.000	EA
Precast Concrete Barrier Rail	204.000	LF
31.33' Precast Concrete Cap, Intermediate Unit, Concrete Pile	2.000	EA
31' Precast Concrete Cap, End Unit, Concrete Pile	2.000	EA
9.25' Precast Concrete Wing	4.000	EA
Loose Riprap (300 lb)	138.000	TON
Geotextile under Riprap (Type V) Non-Woven (AOS < 0.43)	372.000	SY