



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Covington
Project No. SABP-16(01)
Road Name. SEMINARY-SUMRALL

BIDS RECEIVED: 10:00 AM March 18, 2025 in the Chancery Building in Collins MS

Project Description: 0.113 miles of BRIDGE & APPROACHES

Roadway Items:

| | | |
|---|-----------|-----|
| MOBILIZATION | 1.000 | LS |
| CLEARING AND GRUBBING | 1.000 | LS |
| REMOVAL OF BRIDGE @ STA. 95+46.00 | 1.000 | UN |
| REMOVAL OF PIPE (ALL SIZES) | 36.000 | LF |
| UNCLASSIFIED EXCAVATION (FM) | 240.000 | CY |
| BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9) | 2,650.000 | CY |
| GRANULAR MATERIAL (FM OR LVM), (CLASS 5, GROUP C) | 1,270.000 | CY |
| HOT MIX ASPHALT, ST, 12.5 mm | 140.000 | TON |
| HOT MIX ASPHALT, ST, 25 mm | 420.000 | TON |
| 54 " REINFORCED CONCRETE PIPE, CLASS III | 52.000 | LF |
| 54 " REINFORCED CONCRETE PIPE, END SECTION | 2.000 | EA |
| GUARD RAIL, W-BEAM | 52.000 | LF |
| GUARD RAIL, BRIDGE END SECTION, TYPE I | 4.000 | EA |
| GUARD RAIL, TERMINAL END SECTION | 4.000 | EA |
| MAINTENANCE OF TRAFFIC | 1.000 | LS |
| ADDITIONAL CONSTRUCTION SIGNS | 0.000 | SF |
| 4 " WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (90 MILS) | 0.227 | MI |
| 4 " WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (120 MIL) | 1,200.000 | LF |
| TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS | 16.000 | EA |
| REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3) | 4.000 | EA |

EROSION CONTROL ITEMS:

| | | |
|--|---------|-----|
| AGRICULTURAL LIMESTONE | 0.600 | TON |
| COMMERCIAL FERTILIZER (13-13-13) | 0.600 | TON |
| AMMONIUM NITRATE | 0.020 | TON |
| SEEDING | 0.700 | AC |
| VEGETATIVE MATERIALS FOR MULCH | 0.600 | TON |
| SOLID SODDING | 200.000 | SY |
| TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84) | 200.000 | LF |
| WATTLES, 20" DIAMETER | 80.000 | LF |
| LOOSE RIPRAP, 200 LB. | 100.000 | TON |

BRIDGE ITEMS:

| | | |
|------------------------------------|---------|----|
| TEST PILE | 2.000 | EA |
| CONVENTIONAL STATIC PILE LOAD TEST | 0.000 | EA |
| 14 " PRESTRESSED CONCRETE PILING | 750.000 | LF |

| | | |
|---|---------|-----|
| 18 " PRE-FORMED PILE HOLES | 200.000 | LF |
| 40 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR | 18.000 | EA |
| 40 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR | 6.000 | EA |
| PRECAST CONCRETE BARRIER RAIL | 240.000 | LF |
| 31.17 ' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, | 2.000 | EA |
| 31.17 ' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, | 2.000 | EA |
| 9.17' PRECAST CONCRETE WING | 4.000 | EA |
| LOOSE RIPRAP, 300 LB. | 235.000 | TON |
| GEOTEXTILE UNDER RIPRAP , TYPE V, AOS < 0.43 (NON-WOVEN) | 620.000 | SY |