



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Greene
Project No. SABP-21(01)
Road Name. WEST SALEM ROAD

BIDS RECEIVED: Tuesday, July 23, 2024, at 10:00 a.m., in the Boardroom at Leakesville, MS

Project Description: 0.304 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE AT STATION 31+05	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	75.000	LF
UNCLASSIFIED EXCAVATION (FM)	2,005.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	2,565.000	CY
EXCESS EXCAVATION (FM)	805.000	CY
STRUCTURE EXCAVATION	750.000	CY
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B)	1,115.000	CY
CRUSHED STONE, 610	1,895.000	TON
SIZE II STABILIZER AGGREGATE, COARSE	150.000	CY
HOT MIX ASPHALT,(ST)(9.5mm)	281.000	TON
HOT MIX ASPHALT,(ST)(12.5 mm)	490.000	TON
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	1.002	CY
73" X 45" REINFORCED CONCRETE ARCH PIPE,CLASS III	168.000	LF
73" X 45" REINFORCED CONCRETE ARCH PIPE, END SECTION	6.000	EA
GUARD RAIL, W-BEAM	200.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE I THRI-BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	22.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.610	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	3,220.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	30.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	5.200	TON
COMMERCIAL FERTILIZER (13-13-13)	2.600	TON
AMMONIUM NITRATE	0.260	TON
SEEDING	2.600	AC
VEGETATIVE MATERIALS FOR MULCH	5.200	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	3,300.000	LF
WATTLES, 20"	300.000	LF

RIPRAP FOR EROSION CONTROL	150.000	TON
REMOVE AND RESET RIPRAP	100.000	CY
LOOSE RIPRAP, 200 LB.	400.000	TON
GEOTEXTILE UNDER BRIDGE ABUTMENT, NON-WOVEN, TYPE V, AOS (0.21-0.43)	100.000	SY
GEOTEXTILE UNDER RIPRAP, NON-WOVEN, TYPE V, AOS (0.21-0.43)	800.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	1,075.000	LF
18" PRE-FORMED PILE HOLES	220.000	LF
31' PRECAST CONCRETE SLAB UNIT, 3' 6" INTERIOR	6.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3' 6" INTERIOR	18.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3' 6" EXTERIOR	2.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3' 6" EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	302.000	LF
31'-2" PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
31'-4" PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	1.000	EA
31' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	1.000	EA
31'-2" PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	1.000	EA
9.17' PRECAST CONCRETE WING	2.000	EA
9.25' PRECAST CONCRETE WING	2.000	EA
LOOSE RIPRAP, 300 LB.	85.000	TON
GEOTEXTILE UNDER RIPRAP, NON-WOVEN, TYPE V, AOS <0.43	223.000	SY