



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

**County** Lauderdale  
**Project No.** SABP-38(01)  
**Road Name.** Sand Flat Road

**BIDS RECEIVED:** WEDNESDAY, FEBRUARY 12, 2025 AT 10:00 AM IN THE SUPERVISOR'S BOARDROOM AT MERIDIAN, MS

**Project Description:** 0.056 miles of BOX BRIDGE & APPROACHES

**Roadway Items:**

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE AT STA. 19+60.22	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	1,258.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	640.000	CY
CHANNEL EXCAVATION (FM)	183.000	CY
EXCESS EXCAVATION (FM)	300.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B)	390.000	CY
HOT MIX ASPHALT, ST 12.5MM	74.000	TON
HOT MIX ASPHALT, ST 19MM	154.000	TON
CLASS "C" STRUCTURAL CONCRETE	30.000	CY
RIGHT-OF-WAY MARKERS (TYPE II)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (90 MIL)	0.114	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (120 MIL)	600.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	5.000	EA

**EROSION CONTROL ITEMS:**

SOLID SODDING	175.000	SY
EXCELSIOR BLANKET	600.000	SY
HYDROSEEDING	0.560	AC
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	600.000	LF
WATTLES, 20"	100.000	LF
LOOSE RIPRAP, 300 LB.	100.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS<0.43, NON-WOVEN	350.000	SY

**BOX BRIDGE ITEMS:**

BOX BRIDGE CONCRETE, CLASS "BB"	155.870	CY
REINFORCEMENT	23,973.000	LB