



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County	<u>Leake</u>
Project No.	<u>SABP-40(01)</u>
Road Name.	<u>UNION ROAD</u>

<u>BIDS RECEIVED:</u>	<u>MONDAY, APRIL 21, 2025 AT 9:00 AM IN THE SUPERVISOR'S BOARDROOM AT CARTHAGE, MS</u>
------------------------------	--

<u>Project Description:</u>	<u>0.084 miles of BRIDGE & APPROACHES</u>
------------------------------------	---

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 22+00	1.000	UN
REMOVAL OF EXISTING ASPHALT PAVEMENTS (ALL DEPTHS)	917.000	SY
UNCLASSIFIED EXCAVATION (FM)	340.000	CY
EXCESS EXCAVATION (FM)	337.000	CY
CRUSHED STONE (3/4" & DOWN)	950.000	TON
MIXING, SHAPING AND COMPACTION	930.000	SY
HOT MIX ASPHALT, ST, 9.5mm	141.000	TON
ASPHALT FOR PRIME COAT (EA-1)	340.000	GAL
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	0.290	CY
48" REINFORCED CONCRETE PIPE, CLASS III	88.000	LF
48" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
GUARD RAIL, W-BEAM	60.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I" THRIE BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
BRIDGE CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (90 MILS)	0.170	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (120 MILS)	0.170	MI
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	8.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	2.960	TON
COMMERCIAL FERTILIZER (13:13:13)	0.670	TON
AMMONIUM NITRATE	0.150	TON
SEEDING	2.220	AC
VEGETATIVE MATERIALS FOR MULCH	6.660	TON
EXCELSIOR BLANKET	300.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)	1,060.000	LF
WATTLES, 20"	830.000	LF
LOOSE RIPRAP, 200 LB.	892.000	TON

GEOTEXTILE UNDER RIPRAP, (TYPE V, AOS 0.21 - 0.43)	1,873.000	SY
<u>BRIDGE ITEMS:</u>		
TEST PILES	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	910.000	LF
18" PRE-FORMED PILE HOLES	200.000	LF
CONCRETE PILING CUT-OFF, 14"	0.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, 30 DEG SKEW, LT FWD	6.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, 30 DEG SKEW, LT FWD	12.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, LT FWD	2.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, LT FWD	4.000	EA
PRECAST CONCRETE BARRIER RAIL	162.000	LF
36.0' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, 30 DEG SKEW, LT FWD.	2.000	EA
36.0' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, 30 DEG SKEW, LT FWD.	2.000	EA
11.33' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	100.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON WOVEN, AOS 0.21 - 0.43	210.000	SY