



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Marion
Project No. SABP-46(01)
Road Name. OLD RIVER ROAD

BIDS RECEIVED: WEDNESDAY, JANUARY 22, 2025 AT 10:00 AM IN THE BOARDROOM AT COLUMBIA, MS

Project Description: 0.098 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STATION 10+66	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	310.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	1,022.000	CY
CHANNEL EXCAVATION (FM)	185.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	735.000	CY
CRUSHED STONE, SIZE 610	100.000	TON
HOT MIX ASPHALT, ST 19MM	206.000	TON
HOT MIX ASPHALT, ST 9.5 MM	196.000	TON
ASPHALT FOR PRIME COAT (EA-1)	437.000	GAL
GUARD RAIL, W-BEAM	50.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE I THRIE-BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4 " WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.199	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	1,050.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	24.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.700	TON
COMMERCIAL FERTILIZER (13-13-13)	0.850	TON
SEEDING	0.850	AC
VEGETATIVE MATERIALS FOR MULCH	1.700	TON
SOLID SODDING	200.000	SY
EROSION MAT	136.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,100.000	LF
WATTLES, 20"	120.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14 " PRESTRESSED CONCRETE PILING	560.000	LF

18" PRE-FORMED PILE HOLES	130.000	LF
31 ' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	18.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	186.000	LF
31' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
31' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	175.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS < 0.43	417.000	SY