



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Stone
Project No. SABP-66(01)
Road Name. OLD HIGHWAY 26

BIDS RECEIVED: MONDAY, DECEMBER 2, 2024 AT 10:00 AM IN THE BOARDROOM AT WIGGINS, MS

Project Description: 0.201 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST CONCRETE BRIDGE (STA. 14+34)	1.000	UN
REMOVAL OF PAVEMENT	2,155.000	SY
UNCLASSIFIED EXCAVATION (FM)	3,127.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9-8)	1,162.000	CY
GRANULAR MATERIAL (LVM) (CLASS 6, GROUP C)	1,375.000	CY
CRUSHED STONE SIZE 610 (LVM)	90.000	CY
HOT MIX ASPHALT, ST, 9.5mm	257.000	TON
HOT MIX ASPHALT, ST, 12.5mm	529.000	TON
GUARD RAIL, "W" BEAM	75.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I" THRIE BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	10.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4 " WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MIL)	0.403	MI
4 " WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	2,130.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	15.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
GEOTEXTILE UNDER CRUSHED STONE (TYPE V) (NON-WOVEN) (AOS < 0.43)	152.000	SY

EROSION CONTROL ITEMS:

TOPSOIL FOR SLOPE TREATMENT (CONTRACTOR FURNISHED) (LVM)	500.000	CY
SOLID SODDING	500.000	SY
EXCELSIOR BLANKET	500.000	SY
HYDROSEEDING	2.150	AC
EROSION MAT	183.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	2,150.000	LF
WATTLES, 20 "	1,100.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14 " PRESTRESSED CONCRETE PILING	960.000	LF
18 " PRE-FORMED PILE HOLE	455.000	LF

31 ' PRECAST CONCRETE SLAB UNIT, 3 ' - 6 " INTERIOR	24.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3 ' - 6 " EXTERIOR	8.000	EA
PRECAST CONCRETE BARRIER RAIL	248.000	LF
31 ' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	3.000	EA
31 ' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.25 ' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	220.000	TON
GEOTEXTILE UNDER RIPRAP (TYPE V) (NON-WOVEN) (AOS < 0.43)	390.000	SY