



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Washington
Project No. SABP-76(01)
Road Name. CLUB 17 ROAD

BIDS RECEIVED: THURSDAY, APRIL 24, 2025 10:00 AM IN THE OFFICE OF THE CHANCERY COURT AT GREENVILLE, MS

Project Description: 0.161 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE (14+10)	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	972.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	1,222.000	CY
CHANNEL EXCAVATION (FM)	425.000	CY
CRUSHED STONE 825 B	1,396.000	TON
HOT MIX ASPHALT, ST, 12.5 mm	173.000	TON
HOT MIX ASPHALT, ST, 19 mm	345.000	TON
GUARD RAIL, "W" BEAM, COMPLETE-IN-PLACE	31.250	LF
GUARD RAIL, CABLE ANCHOR, TYPE 1	12.500	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "G", "W" BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	2.000	EA
SPECIAL SECTIONS, ROUNDED "W" END SECTION	12.500	LF
RIGHT-OF-WAY MARKERS (TYPE II)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MIL)	0.333	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (60 MIL)	1,799.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 MIL)	107.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	3.000	TON
COMMERCIAL FERTILIZER (13:13:13)	1.500	TON
SEEDING	1.500	AC
VEGETATIVE MATERIALS FOR MULCH	4.500	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)	1,545.000	LF
WATTLES, 20"	320.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
18" PRESTRESSED CONCRETE PILING	1,720.000	LF
22" PRE-FORMED PILE HOLES	360.000	LF
BRIDGE CONCRETE, CLASS A	86.000	CY

REINFORCEMENT	15,720.000	LB
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, 30 DEGREE SKEW, RT. FWD.	20.000	EA
31' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR, 30 DEGREE SKEW, RT. FWD.	10.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEGREE SKEW, RT. FWD.	10.000	EA
PRECAST CONCRETE BARRIER RAIL	310.000	LF
LOOSE RIPRAP, 300 LB.	367.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS < 0.43	709.000	SY