



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Jones
Project No. SAP-34(79)
Road Name. ORANGE ROAD

BIDS RECEIVED: FRIDAY, AUGUST 2, 2024 10:30 a.m. in the SUPERVISOR'S BOARDROOM at LAUREL, MS

Project Description: 0.208 miles of BRIDGE & APPROACHES

Roadway Items:

| | | |
|--|-----------|-----|
| MOBILIZATION | 1.000 | LS |
| CLEARING AND GRUBBING | 1.000 | LS |
| REMOVAL OF BRIDGE @ STA. 420+06 | 1.000 | UN |
| UNCLASSIFIED EXCAVATION (FM) | 1,335.000 | CY |
| BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9-6) | 4,061.000 | CY |
| GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B)" | 936.000 | CY |
| CRUSHED STONE | 592.000 | TON |
| HOT MIX ASPHALT, (ST) (19 mm) | 549.000 | TON |
| HOT MIX ASPHALT, (ST) (9.5 mm) | 203.000 | TON |
| GUARD RAIL, W" BEAM" | 50.000 | LF |
| GUARD RAIL, BRIDGE END SECTION, TYPE I" THRIE BEAM" | 4.000 | EA |
| GUARD RAIL, TERMINAL END SECTION | 4.000 | EA |
| RIGHT-OF-WAY MARKERS (TYPE I) | 9.000 | EA |
| MAINTENANCE OF TRAFFIC | 1.000 | LS |
| ADDITIONAL CONSTRUCTION SIGNS | 0.000 | SF |
| 4 WIDE COLD PLASTIC EDGE STRIPE" (CONTINUOUS WHITE) | 0.045 | MI |
| 4 WIDE COLD PLASTIC TRAFFIC" STRIPE (CONTINUOUS YELLOW) | 240.000 | LF |
| 4 WIDE THERMOPLASTIC EDGE STRIP" (CONTINUOUS WHITE) (60 MIL) | 0.371 | MI |
| 4 WIDE THERMOPLASTIC TRAFFIC" STRIPE (CONTINUOUS YELLOW) (90 MIL) | 1,961.000 | LF |
| TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS | 28.000 | EA |
| REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3) | 4.000 | EA |
| REFLECTORIZED TRAFFIC DELINEATOR SIGN (ENCAPSULATED LENS) | 18.000 | EA |
| GEOTEXTILE FABRIC UNDER BRIDGE END TREATMENT TYPE V, AOS 0.21 - 0.84 | 134.000 | SY |

EROSION CONTROL ITEMS:

| | | |
|--|-----------|-----|
| AGRICULTRURAL LIMESTONE | 3.800 | TON |
| COMMERCIAL FERTILIZER (13:13:13) | 1.900 | TON |
| AMMONIUM NITRATE | 0.190 | TON |
| SEEDING | 1.900 | AC |
| VEGETATIVE MATERIALS FOR MULCH | 5.700 | TON |
| TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84) | 1,886.000 | LF |
| WATTLES, 12 in diamter | 200.000 | LF |

BRIDGE ITEMS:

| | | |
|------------------------------------|-------|----|
| TEST PILE | 2.000 | EA |
| CONVENTIONAL STATIC PILE LOAD TEST | 0.000 | EA |

| | | |
|---|---------|-----|
| 14 PRESTRESSED CONCRETE PILING" | 670.000 | LF |
| 18 PRE-FORMED PILE HOLES" | 570.000 | LF |
| 40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR | 18.000 | EA |
| 40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR | 6.000 | EA |
| PRECAST CONCRETE BARRIER RAIL | 240.000 | LF |
| 31'- 2 PRECAST CONCRETE CAP ,INTERMEDIATE UNIT CONCRETE PILE | 2.000 | EA |
| 31'- 2 PRECAST CONCRETE CAP ,END UNIT CONCRETE PILE | 2.000 | EA |
| 9.17' PRECAST CONCRETE WING | 4.000 | EA |
| LOOSE RIPRAP, 300 LB. | 90.000 | TON |
| GEOTEXTILE FABRIC UNDER RIPRAP NON-WOVEN TYPE V, AOS - < 0.43 | 166.000 | SY |