



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

**County** Lawrence

**Project No.** SAP-39(18)M

**Road Name.** SITE "A" THRU "G"

**BIDS RECEIVED:** TUESDAY, JANUARY 21, 2025 AT 10:00 AM at the County Boardroom in

**Project Description:** MONTICELLO, MS 0.394 miles of MAINTENANCE (OTHER THAN BRIDGE)

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF HEADWALLS	5.000	UN
REMOVAL OF CONCRETE DRIVEWAY	12.000	SY
REMOVAL OF PIPE (ALL SIZES)	156.000	LF
UNCLASSIFIED EXCAVATION (FM)	624.000	CY
BORROW EXCAVATION (CONTRACTOR FURNISHED, LVM, CLASS 7)	865.000	CY
EXCESS EXCAVATION (LVM)	156.000	CY
STRUCTURE EXCAVATION	531.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	30.000	CY
CRUSHED STONE (SIZE 610) (LVM)	144.000	CY
SIZE II STABILIZER AGGREGATE, COARSE	130.000	CY
HOT MIX ASPHALT, ST 9.5mm	34.000	TON
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	45.730	CY
REINFORCING STEEL	2,139.000	LB
42" REINFORCED CONCRETE PIPE, CLASS III	48.000	LF
54" REINFORCED CONCRETE PIPE, CLASS III	168.000	LF
42" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
54" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
88" X 54" REINFORCED CONCRETE ARCH PIPE, CLASS III	48.000	LF
88" X 54" REINFORCED CONCRETE ARCH PIPE, END SECTION	2.000	EA
GUARDRAIL, W-BEAM	520.000	LF
GUARDRAIL, TERMINAL END SECTION, NON FLARED	8.000	EA
CONCRETE DRIVEWAY	12.000	SY
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.041	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	214.000	LF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	8.000	EA
LOOSE RIPRAP, 200 LB.	802.000	TON
GEOTEXTILE UNDER LOOSE RIPRAP, TYPE V, AOS <0.43 (NON-WOVEN)	945.000	SY

EROSION CONTROL ITEMS:

COMMERCIAL FERTILIZER (13-13-13)	0.154	TON
SEEDING	0.154	AC
VEGETATIVE MATERIALS FOR MULCH	0.308	TON

TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)  
WATTLES, 20"

622.000

LF

160.000

LF