



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Leflore
Project No. SAP-42(66)
Road Name. COUNTY ROAD NO. 545

BIDS RECEIVED: MONDAY, JANUARY 27, 2025 AT 3:00 PM IN THE BOARDROOM AT GREENWOOD, MS

Project Description: 0.152 miles of BOX CULVERT & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 229+67	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	433.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	2,115.000	CY
CHANNEL EXCAVATION (FM)	210.000	CY
STRUCTURE EXCAVATION	400.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (LVM), (CLASS 4, GROUP "B")	137.000	CY
CRUSHED STONE(SIZE 610)	838.000	TON
CRUSHED STONE (SIZE 57)	210.000	TON
PORTLAND CEMENT	842.000	CWT
SOIL-CEMENT-WATER MIXING, MULTIPLE PASS MIXERS	2,489.000	SY
HOT MIX ASPHALT, ST, 12.5MM	300.000	TON
CLASS "B" STRUCTURAL CONCRETE	139.850	CY
REINFORCING STEEL	28,911.000	LB
18" REINFORCED CONCRETE PIPE, CLASS III	80.000	LF
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	16.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (90 MILS)	0.304	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (120 MILS)	0.152	MI
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	10.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	2.740	TON
COMMERCIAL FERTILIZER (13:13:13)	1.370	TON
AMMONIUM NITRATE	0.140	TON
SEEDING	1.370	AC
VEGETATIVE MATERIALS FOR MULCH	2.740	TON
EXCELSIOR BLANKET	1,175.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	600.000	LF
WATTLES, 12"	250.000	LF
LOOSE RIPRAP, 300 LB.	240.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN	745.000	SY