



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

**County** Madison  
**Project No.** SAP-45(18)S  
**Road Name.** Virilia Road

**BIDS RECEIVED:** TUESDAY, JANUARY 21, 2025 AT 10:00 AM IN THE SUPERVISORS' BOARDROOM AT CANTON, MS

**Project Description:** 1.913 miles of RESEAL

**Roadway Items:**

MOBILIZATION	1.000	LS
EXCESS EXCAVATION (FM)	128.000	CY
GRANULAR MATERIAL (LVM), (CLASS 5, GROUP C )	95.000	CY
HOT MIX ASPHALT BASE COURSE (BB-1)	256.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	118.000	SY
POLYMERIZED-EMULSIFIED ASPHALT, GRADE CRS-2P	20,301.000	GAL
SEAL AGGREGATE COVER MATERIAL, SIZE 89, TYPE CRUSHED STONE	238.000	CY
SEAL AGGREGATE COVER MATERIAL, SIZE 7, TYPE CRUSHED STONE	238.000	CY
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) ( 60 mils)	3.829	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) ( 90 mils )	0.777	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 mils)	13,264.000	LF
THERMOPLASTIC DETAIL STRIPE (4 " EQUIVALENT LENGTH) (WHITE) ( 60 mils )	504.000	LF
THERMOPLASTIC DETAIL STRIPE (4 " EQUIVALENT LENGTH) (YELLOW) ( 60 mils )	150.000	LF
THERMOPLASTIC LEGEND (WHITE) ( 120 mils )	122.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	169.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	6.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	3.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	12.000	EA
ASPHALT FOR FOG SEAL, GRADE CHPF-1	2,537.000	GAL