



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS

County Madison
Project No. SAP-45(22)M
Road Name. Pear Orchard Road

BIDS RECEIVED: TUESDAY, MARCH 4, 2025 AT 10:00 AM IN THE BOARDROOM AT CANTON, MS

Project Description: 1.433 miles of MAINTENANCE (OTHER THAN BRIDGE)

Roadway Items:

MOBILIZATION	1.000	LS
UNCLASSIFIED EXCAVATION (FM)	282.000	CY
GRANULAR MATERIAL (LVM), (CLASS 5, GROUP C)	84.000	CY
HOT MIX ASPHALT BASE COURSE, BB-1	564.000	TON
HOT BITUMINOUS PAVEMENT SURFACE COURSE (SC-1)(TYPE 8)	2,256.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	27,334.000	SY
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
6" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP WHITE) (90 mils)	0.037	MI
6" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 mils)	2.896	MI
6" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 mils)	11,838.000	LF
THERMOPLASTIC DETAIL STRIPE (4 " EQUIVALENT LENGTH) (WHITE) (60 mils)	4,263.000	LF
THERMOPLASTIC DETAIL STRIPE (4 " EQUIVALENT LENGTH) (YELLOW) (60 mils)	3,473.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 mils)	1,035.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 mils)	674.000	SF
RED-CLEAR REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	36.000	EA
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	161.000	EA
VEHICLE LOOP ASSEMBLIES	2,916.000	LF