



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS

County Marion
Project No. SAP-46(19)M
Road Name. "A" THRU "J"

BIDS RECEIVED: TUESDAY, FEBRUARY 18, 2025 AT 10:00 AM IN THE BOARDROOM AT COLUMBIA, MS
Project Description: 46.54 miles of MAINTENANCE (OTHER THAN BRIDGE)

Roadway Items:

MOBILIZATION	1.000	LS
UNCLASSIFIED EXCAVATION (FM)	120.000	CY
GRANULAR MATERIAL (LVM), (CLASS 4, GROUP B)	1,000.000	CY
HOT MIX ASPHALT, ST 19mm	1,163.000	TON
HOT MIX ASPHALT, ST 9.5mm	1,179.000	TON
ULTRA THIN ASPHALT PAVEMENT	4,923.000	TON
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 mils)	92.077	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 mils)	8.076	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 mils)	437,984.000	LF
THERMOPLASTIC DETAIL STRIPE (4 " EQUIVALENT LENGTH) (WHITE) (60 mils)	6,445.000	LF
THERMOPLASTIC DETAIL STRIPE (4 " EQUIVALENT LENGTH) (YELLOW) (90 mils)	1,520.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 mils)	3,060.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 mils)	2,097.000	SF
TWO-WAY CLEAR REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	2,291.000	EA
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	3,324.000	EA
ASPHALT FOR FOG SEAL, GRADE CHPF-1	52,829.000	GAL