



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Newton
Project No.	SAP-51(75)
Road Name.	Newton-Bethel Road

BIDS RECEIVED: FRIDAY, JANUARY 30, 2026 AT 10:00 AM IN THE BOARDROOM AT DECATUR, MS

Project Description: 0.108 miles of BOX BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 11+95.59	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	1,578.000	CY
MUCK EXCAVATION (FM)	339.000	CY
BORROW EXCAVATION (CONTRACTOR FURNISHED, FME, CLASS 9-6)	626.000	CY
CHANNEL EXCAVATION (FM)	173.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B)	699.000	CY
CRUSHED STONE, SIZE 825	213.000	TON
HOT MIX ASPHALT, (ST) (9.5MM)	123.000	TON
HOT MIX ASPHALT, (ST) (19MM)	375.000	TON
FILTER MATERIAL FOR FILTER BEDS, TYPE A	610.000	CY
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	16.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MIL)	0.218	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	1,150.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	15.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	2.160	TON
COMMERCIAL FERTILIZER (13:13:13)	1.080	TON
AMMONIUM NITRATE	0.108	TON
SEEDING	1.080	AC
VEGETATIVE MATERIALS FOR MULCH	2.160	TON
SOLID SODDING	100.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS-0.15-0.43)	1,353.000	LF
WATTLES, 12"	200.000	LF
LOOSE RIPRAP, 100 LB.	30.000	TON
LOOSE RIPRAP, 200 LB.	144.000	TON
GEOTEXTILE FABRIC UNDER RIPRAP, TYPE V, AOS (0.21-0.43)	229.000	SY

BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"	329.400	CY
REINFORCEMENT	53,261.000	LB