



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)  
AND  
COUNTY BOARD OF SUPERVISORS

**County** Warren

**Project No.** SAP-75(31)M

**Road Name.** OAK RIDGE ROAD

**BIDS RECEIVED:** 10:00 AM County Boardroom Vicksburg Ms. Tuesday November 26, 2024

**Project Description:** 3.564 miles of OVERLAY

**Roadway Items:**

MOBILIZATION	1.000	LS
UNCLASSIFIED EXCAVATION (FM)	213.000	CY
GRANULAR MATERIAL, (CLASS 5, GROUP C )	1,052.000	TON
HOT MIX ASPHALT BASE COURSE, (BB-1)	421.000	TON
HOT BITUMINOUS PAVEMENT LEVELING COURSE (BC-1)(TYPE 8)	3,613.000	TON
HOT BITUMINOUS PAVEMENT SURFACE COURSE (SC-1)(TYPE 8)	2,409.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	67.000	SY
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) ( 60 Mil )	7.135	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) ( 90 Mil )	37,716.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 Mil)	513.000	LF
TWO-WAY CLEAR REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	156.000	EA
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	315.000	EA